



DUBBO BASE HOSPITAL DEVELOPMENT

MAR - NOV 2018
HANSEN YUNCKEN
\$2.76 M



DEMEX was engaged as the demolition contractor for Stages 3 and 4 of the Dubbo Base Hospital Redevelopment Project. Demolition works included deconstruction of the iconic George Hatch Building, S Block and multiple other structures.

Asbestos removal enclosures were constructed to ensure the safety of workers and hospital users.

The staged works were conducted in the immediate vicinity of live hospital operations which required significant coordination to ensure hospital users were not impacted. Detailed manual separation works, utilising mobile cranes, were completed to safely isolate and secure the live hospital areas from the structures being demolished.

Prior to commencement of the demolition works, a comprehensive hazmat removal program was completed which identified significantly degraded friable asbestos lagged pipes in highly visible external locations.

