






DUBBO HOSPITAL WESTERN CANCER CENTRE



MAR - APR 2020 LIPMAN GROUP \$0.5 M



Working within live hospital grounds required detailed coordination and open communication with key stakeholders throughout the project to ensure hospital users were not adversely impacted.

DEMEX faced logistical challenges due to the proximity of the building's exterior wall to the adjacent road.

Traffic control was implemented to create the appropriate exclusion zone allowing for the demolition to take place safely.

The top half of the exterior wall was dismantled manually to maintain its stability before demolition with excavators could continue works.

Demolition of the plant room, which was located on the second floor and was conducted while the hospital remained operational.

Works were carried out following a precise methodology to ensure minimal impact to the hospital staff and patients. Demolition of the water tower was executed with effective vibration monitoring to minimise any disruption to hospital operations.

All works occurred with COVID protocols in place.

